

Golden Crown
The Lodge, South Street
Cuckfield Park
Cuckfield, RH17 5AB
alfred@goldencrowntree.com
01444 685328

**Cuckfield Parish Council** 

The Queen's Hall, High Street, Cuckfield, West Sussex,, RH17 5EL. **Site Address** 

The Queen's Hall, High Street, Cuckfield,, , RH17 5EL. Job Number: #4838 VAT Number: 298 2508 63 Estimate Date: 6th Mar 2023 Valid Until: 5th May 2023

### **Estimate**

Name Quantity Price Total

## 2.4m Chainlink framework along the boundary

Supplying and installing Angle iron 40 x 40 x 5mm green intermediate posts dug in and concreted for 2.4m height and tensioned. 4 new straining wires pulled to supply strength to the trees.

£1,380.06

### Ramp from top hedge area for access

Ramp from top hedge area for access, using 150mm x 50mm timber to shutter the ramp and set gradient and heights. with compacted mot, then screeded with mortar for the ramp base. Using blocks supplied, block paving laid over the area for finished surface. Kiln dried sand brushed into finish.

£830.60

# Top area dug out and leveled

Top area dug out and levelled with a digger. Soil to stay on site and be reused in the raised beds.

£1,120.00

## Retaing wall round the dug out area using 6 \* 2 timber

Supplying and installing 150mm x 50mm timber around the top dug out area to retain the bank. On 100mm x 100mm posts dug in around the side to support the the timber. Posts dug in and concreted.

£1,309.67

**Subtotal** £4,640.33 **VAT Amount** £928.06

Total £5,568.39

Estimate #4838 (Version 3) Page 1/2

Name Quantity Price Total

If you would like to go ahead, please let us know in writing (email/letter/text) so that we may arrange a mutually convenient date and time for your work to be done. Estimates are valid for six weeks from their date of issue, after which time the contractor is entitled to draw up a new estimate/amend costs.

Please understand that in accepting our estimate you agree to our Terms and Conditions and that payment becomes due on completion of works (www.goldencrowntree.com).

For complex works over £5000 a 50% Deposit is required two weeks prior to starting work.

A 50% Deposit will be asked for any jobs involving buying materials, hiring equipment, etc. in good time prior to commencing.

VAT Registration Number: 298 2508 63

Estimate #4838 (Version 3) Page 2/2