



**CENTRAL SUSSEX
CONSTRUCTION &
ELECTRICAL LTD**

Central Sussex Construction And Electrical Ltd

Unit 1C Hillmans Business Park
Chapel Road, Twineham
West Sussex
RH17 5NN

VAT Number: 206 6774 00
T: 01444 881584
E: Info@cs-electrical.com

Cuckfield Parish Council
United Kingdom

Estimate

Quote Number: 2537
Quote Date: 11th Feb '24
Valid For: 30 Days
Account: CUCK03
Quote Ref: Queens Hall

Qty	Description	Rate	Total
-----	-------------	------	-------

Thank you for allowing Central Sussex Construction and Electrical Ltd to quote for the following work:

Toilet refurbishment (Queens Hall)

Qty	Description	Rate	Total
	<p>Females</p> <p>Full strip out of everything but leaving ceiling grid.</p> <p>Uplift old vinyl floor</p> <p>Install new upstands for flooring</p> <p>Primer floor as required and pour levelling compound</p> <p>Install new polysafe welded flooring (to be chosen) to all areas with 100mm upstand for easy cleaning.</p> <p>Supply and install new polyrey(colours tbd) will do a visual when colours decided</p> <ul style="list-style-type: none"> - Duct panel for cubicle x3 - Cubicle, doors and pillistars x3 - New duct panel and worktop for sinks - New handryer x1 - Toilet with soft close seat x3 - Conceled cistern behind duct panel x3 -howdens/polyrey worktop to match colour scheme - 2 x iflo countertop basin with mixer tap. <p>All plumbing to have new pipework valves and traps for easy maintenance.</p> <p>Decoration to all in clean extreme on walls and crown satinwood to woodwork (colours tbd)</p> <p>Ceiling to have</p> <ul style="list-style-type: none"> 4 x new led panel lights 600x600 1 x round led light 2 x emergency lights with test switch 30 x new wipe down hygiene tiles 600x600 <p>Remove existing tiles and plaster as required</p> <p>Install white trovex pvc wall cladding for easy cleaning to where tiles were.</p> <p>Install splashback for sink with 2 new mirrors and soap dispensers.</p> <p>New double stelrad radiator with trv</p>		
	<p>Disabled cloakroom</p> <p>Remove toilet (to be refitted)</p> <p>Uplift old vinyl flooring</p> <p>Re level and primer as required</p> <p>Install new polysafe welded floor with 100mm upstand for easy cleaning.</p> <p>Box in pipes where possible keeping to DDA regulations</p> <p>Decoration to entire room in crown clean extreme and satin wood to woodwork.</p> <p>Install Led polo light on ceiling</p>		

Qty	Description	Rate	Total
	<p>Males</p> <p>Full strip out of everything but leaving ceiling.</p> <p>Uplift old vinyl floor</p> <p>Install new upstands for flooring</p> <p>Re level and primer floor as required</p> <p>Install new polyfloor welded flooring (to be chosen) to all areas with 100mm upstand for easy cleaning.</p> <p>Supply and install new Polyrey panels (colours tbd)</p> <ul style="list-style-type: none"> - Duct panel for cubicle - Cubicle, door and end panel. - New duct panel and worktop for sinks - New floor to ceiling duct panel for urinals. - 2 x urinal flush and cisterns - 4 x new urinals - Toilet with soft close seat - Concealed cistern behind duct panel. <p>--howdens/polyrey worktop to match colour scheme</p> <ul style="list-style-type: none"> - 2 x iflo countertop basin with mixer tap. <p>All plumbing to have new pipework valves and traps for easy maintenance.</p> <p>Decoration to all woodwork in crown satin wood and clean extreme on walls. (colours tbd)</p> <p>New handryer x1</p> <p>New double stelrad radiator with trv</p> <p>4x new led panels</p> <p>1x round led</p> <p>2 x emergency lights with test switch</p> <p>30 x new wipe down hygiene tiles 600x600</p> <p>Clad over existing tiles with white trovex pvc wall cladding for easy cleaning.</p> <p>Install splashback for sink with 2 new mirrors and soap dispensers.</p>		
1	Labour and Materials	38,477.12	38,477.12

Total Net Amount: £38,477.12

VAT @ 20%: £7,695.42

Quote Total: £46,172.54