



KELLY ENGINEERING SOLUTIONS LTD

Company No: 9345172

Quote

QUOTE #QH03Q
DATE: MAY 28, 2026

Longfields, Ditchling Road, Wivelsfield, East Sussex, RH17 7RF
Phone 07971 607923
k.kelly.contracts@hotmail.com

TO Noemi Ripert
Queens Hall
High Street
Cuckfield
RH17 5EL

To construct a 6m long ramp with a 1.2m drop with timber edges, compacted stone and concrete surface, both side with Alvin Keylock railings installed, with some tree removal	£3357
Labour x 5 days @ £225:	£1,125
Materials: 6x2 timber edging, timber pegs to set in in post mix to secure edges, type1 filling, ballast and concrete to cap	£732
Alvin key lock handrail	£1500

Although this information has the heading of a quote, due to ongoing changes to material prices, that aspect of the calculations is based on the time in which it was compiled and therefore can be subject to change.

THANK YOU FOR YOUR INTEREST IN OUR BUSINESS!