

**From:** [REDACTED]  
**Sent:** Thursday, September 7, 2023 11:50 AM  
**To:** [REDACTED]  
**Cc:** [REDACTED]  
**Subject:** RE: Repairs to Cuckfield Skate Bowl

Sam,

Thank you for your enquiry, and please find our quotation as follows for maintenance works at Cuckfield Skatepark.

Provide RAMS, close site, seal off with tape, erect safety signage.

- A2 – Import 2 tonnes of top soil, lightly compact around trip hazard areas and seed.
- A3 – Remove rust to bare metal, prepare and paint litter bin with Green (approx. ral 6005) lead free paint.
- A4 – Cut back and remove vegetation to create a 2mtr safety zone, top soil and seed.
- A5 – Design and install (onto existing post) safety signage to BSEN14974-2019.
- P1 – Cut and break out two areas of concrete (approx. 300mmx100mmx150mm) Replace with site mixed concrete, hand finish and seal.
- P2 – Carefully grind a radius edge and treat with cold galv.
- P3 – Weld steel RSA sections, carefully grind a radius edge and treat with cold galv.
- P5 – Weld steel RSA sections, carefully grind a radius edge and treat with cold galv.

Price: £7,850 + vat  
Lead Time: 4 Weeks  
Works Duration: 3 Days

I trust the above is competitive and look forward to hearing from you asap.

Best Regards

[REDACTED]

[REDACTED]

W: [www.gravityparks.co.uk](http://www.gravityparks.co.uk)

[REDACTED]

A: Gravity Engineering Ltd, 1 Larkspur Drive, Marchwood, Hampshire, SO40 4JX



The opinions expressed are those of the individual and not the Company. Internet communications are not secure and therefore the company does not accept legal responsibility for the contents of this message. The information contained in this email message is confidential. It is for the exclusive use of the intended person(s) and not for passing on without agreement. If you are not the intended person you are hereby notified that any disclosure, circulation, distribution or copying of this email is strictly prohibited.