



██████████: Bill of Quantities
 Cuckfield Churchyard 2020

ESTIMATE

Item	Description	Qty	Unit	Rate	Value
	<u>Cuckfield Churchyard Footpath Improvements</u>				
	A, B & C				
	Lay approximately 1200mm wide brick clay pavers and sand bedding as described laid across the path on existing tarmac paving including excavating at edges to achieve width and afterwards backfill with soil and grass seed.	125	m	159.59	19,948.75
	West Lychgate				
	Break out and excavate existing tarmac paving and bed under for approximately 200mm and remove from site.	41	m2	38.53	1,579.73
	Lay clay pavers on sand bed as described between two areas of stone paving laid across the path.	41	m2	103.42	4,240.22
	Outside West Church Door				
	Break out and excavate existing tarmac to existing stone paving and bed under for approximately 200mm and remove from site.	125	m2	38.53	4,816.25
	Lay clay pavers and sand bed as described to falls and cross falls and to abut adjacent paver levels, laid to herringbone pattern.	125	m2	116.20	14,525.00
	Extra over for cutting around buttresses and projections around entrance door.	17	m	75.73	1,287.41
	Extra over any paving for working around gullies and raising and jointing to new levels in centre of paving.	1	nr	151.48	151.48
	Ditto to edge of paving	3	nr	151.48	454.44



[Redacted]: Bill of Quantities Estimate Summary
Cuckfield Churchyard 2020

Item	Description	Qty	Unit	Rate	Value
*	ESTIMATE				47,003.28
	<u>Total for Cuckfield Churchyard 2020</u>				47,003.28